



ENGINEERING CELL

Delhi Technological University
ahbad Daulatpur, Bawana Road, Delhi-110042

File No: DTU/108/2026-Engg. Cell / 1441

Dated: 07.08.2026

NOTICE INVITING QUOTATION

The Chief Project Officer, Engineering Cell, DTU invites, on behalf of Delhi Technological University, sealed percentage rate quotations from Contractors up to 03.00 PM on 21.08.2026 for the following works, which shall be opened at 03:30 PM on the same day. Schedule of work along with terms and conditions can be obtained from office of the Chief Project Officer/DTU on all working days by submitting an application along with a copy of G.S.T. No. or PAN Card up to 02:00 PM on 21.08.2026.

S. No.	Name of Work	Estimated Cost (Rs.)	Time Allowed	Last date of Receipt of Quotation
1.	Providing and fixing of shed on the windows on the Rooftop of the central library at DTU Campus, Delhi.	2,52,277/-	30 days	21.08.2026

TERMS & CONDITIONS: -


- The work shall be carried out as per CPWD specifications and as per direction of Engineer-in-Charge.
- The rates quoted should be inclusive of all the taxes and duties & nothing extra shall be paid.
- The work is to be complete as per the given timeline.
- No T&P shall be issued to the firm by the department.
- Necessary recoveries shall be made from the bill, Water charges @1% and Electricity Charges @1% shall be deducted from the bill.
- Penalty on account of delay of the work (if any) may be imposed @ 500/- per day or as per the direction of Engineer-In-Charge.
- Material should use only as per approved material list as attached.
- All the damages and overheads for necessary arrangements shall be borne by the contractor. Nothing shall be paid extra on any account.


Enclosure: 1. Schedule of work (02 Nos.)

2. List of approved makes (02 Nos.)




Copy to: -

1. Registrar, DTU
2. Sr. Account Officer-1, DTU
3. J.E. (Civil)
4. DTU website
5. Notice Board
6. Guard File


7/8/2026
Executive Engineer
DTU Campus, Bawana Road


07/08/26
AE (Civil), DTU

Schedule of Quantity						
Name of work :- Providing and fixing of shed on the windows on the Rooftop of the central library at DTU Campus, Delhi.						
Sr. No.	DSR 2023	DESCRIPTION OF ITEM	QTY.	Unit	RATE (Rs.)	AMOUNT (Rs.)
1	10.16	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete.				
1.1	10.16.3	Electric resistance or induction butt welded tubes	696.00	Kg	194.40	135302.40
2	10.19	Providing and fixing mild steel round holding down bolts with nuts and washer plates complete.	100.00	Kg	97.20	9720.00
3	13.62	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade :				
3.1	13.62.1	Two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture	100.00	Sqm	226.25	22625.00
4	15.28	Dismantling roofing including ridges, hips, valleys and gutters etc., and stacking the material within 50 metres lead of:				
4.1	15.28.1	G.S. Sheet/ Profile sheet/Gurtter etc.	50.00	Sqm	164.95	8247.50
TOTAL						175894.90
Less Correction Factor @ 0.973%						171145.74
Add cost index @ 4.03 % as per CPWD order						6897.17
Total						178042.91
5	NSR	Providing and fixing multi walled thermo clear glass type 10mm thick clear of required blue, brown or green colour etc. polycarbonate multi walled sheet of required brand such as GE of Polygal make or equivalent as per approved by Engineer-in-Charge. The shet shall be fixed on tubular stel structure with 25 micron thick powder coated aluminium Alcox or equivalent section of size 60x18*2mm and weight not less than 0.462kg/m and weather proof Neoprene or EPDM rubber gasket on both side of joints and top, so as to make the whole structure water tight as per approved design/drawings. The aluminium section shall be fixed on joints and both end of sheet to fixed the sheet rigidly on steel frame structure. The weather proof neoprene and aluminium profile shall be fixed and sealed with silicon scalene to make the joints fully water proof. The open over head end of polycarbonate sheet to be sealed with powder coated aluminium channel of 10x10x1.5mm thick and weight not less than 0.2kg/m. the polycarbonate sheet and profile shall be fixed with self-taping and self-drilling 50mm long screws fixed not more than 150mm center to center. The rate shall be inclusive of cost of all material involved such as	50.00	Sqm	1484.68	74234.00

	polycarbonate sheet, aluminium profile, aluminium channel, EPDM gasket, self-taping screws, nut bolts, silicon sealant or any other material required for fixing the sheet but excluding the cost of steel structure which shall be aluminium profile. Hoisting in position etc. complete as per direction of Engineer-in-charge. The rate shall also include the cost of all T&P and safety precautions required during execution of the work. The work shall be completed in all respect as per design/drawing and direction of Engineer-in-charge. (Finished curved surface area of polycarbonate sheet end to end of roofing shall be measured in square meter for the purpose of the payment.				
				Total (B)	74234.00
				Total (A+B)	252277.00
 Junior Engineer (Civil)	 A.E. (Civil)	 Executive Engineer			

C/15

LIST OF APPROVED MAKES OF MATERIALS [CIVIL WORK]

S.NO.	MATERIAL	MANUFACTURERS NAME
	CIVIL ITEMS	
1.	CEMENT	ACC, ULTRATECH, AMBUJA, J.K., LAFARGE, BIRLA, CCI, JK LAKSHMI
2.	REINFORCEMENT STEEL-TMT BARS-FE-500D GRADE	SAIL, TATA STEEL, RINL, JSW, JSPL
3.	STRUCTURAL STEEL SECTIONS	SAIL, TISCO, RINL, JSW, JINDAL STEEL & POWER, JIN DAL, TATA
4.	STRUCTURAL STEEL TUBES/PIPES	JINDAL, TATA, APL APOLLO, ELECTRO STEEL, G.S.F., PRAKASHSURYA, LLOYDS
5.	LGSF VENDORS	M/S INTERARCH BUILDING PRODUCTS PVT. LTD., M/S TATA BLUESCOPE STEEL LTD., M/S MGI INDIA PVT. LTD., M/S JSPL, M/S EVEREST INDUSTRIES LTD., M/S WOOTZ BUILDSYS LLP., M/S EPACK POLYMERS.
6.	READY MIXED CEMENT CONCRETE	ACC, LAFARGE, ULTRATECH, SHREE, ALCHON, L&T GRASIM, NSCONCRETE, RMC READYMIX (INDIA), SHAILA ENTERPRISES, RDC CONCRETE, TECHNO PRIME RMC PVT LTD, VK READY MIX CONCRETE, ASHTECH, SHRI RAM READY MIX CONCRETE
7.	ANTI-TERMITE TREATMENT AGENCY	PEST CONTROL INDIA LTD, GODREJ PEST CONTROL, CAPITAL PEST CONTROL (INDIA)
8.	CHEMICAL TO BE USED FOR 20% E.C.ANTI-TERMITE TREATMENT	DE-NOCIL AND BAYER
9.	SHUTTERING PLY	GREENPLY SHUTTERING PLY, ARCHID SHUTTERING PLY, EURO SHUTTERING PLY
10.	SUPERPLASTICIZERS	MC BAUCHEMIE/FOSROC/SIKA/BASF/CHRYSO/VELOSIT/PIDILITE
11.	WHITE CEMENT	BIRLA WHITE, J.K. WHITE
12.	AAC BLOCK	SHREE, INSTABLOCK, BILTECH, MAGICRETE, SIPROX, BIRLA AEROCON, J.K., CLAVECON INDIA PVT. LTD., J.K. LAKSHMI, B.G. SHIRKE/INDO BHUTANCONSTRUCTION SOLUTION, ULTRATECH XTRALITE,
13.	BLOCK JOINTING MORTAR	JK LAKSHMI, BIRLA AEROCON SMARTFIX, MYK SCHOMBURG, ULTRATECH, FERROUSCRETE, ARDEX
14.	GLAZED CERAMIC TILES	RAK CERAMICS, SOMANY, KAJARIA, NITCO, ORIENT BELL,JOHNSON, ASIAN (AGL)
15.	VITRIFIED TILES	RAK CERAMICS, SOMANY, KAJARIA, ORIENT BELL, JOHNSON,ASIAN(AGL), RESTILE
16.	WALL PUTTY	JK WHITE, BIRLA WHITE, ASIAN, BERGER, BIRLA, JSW
17.	PLASTER OF PARIS	JK LAKSHMI, SAKARNI, SHRIRAM, NIRMAN
18.	GYPSUM PLASTER	SAINT GOBAIN, SAKARNI, J.K. LAKSHMI
19.	ANCHOR PLUG SOIL/ ROCK ANCHOR	BBR, VSL, FREYSSINET

AS
KOL

L *B*

C/14

20.	PORCELAIN TILES	JOHNSON, ASIAN(AGL)
21.	CHILQUERED TILE	NITCO, ULTRA, UNISTNOE, MODERN
22.	CC PAVERS, PRECAST CC KERB STONE, CC TILES, RCC SLAB	NITCO, BHARAT, HINDUSTAN, ULTRA, KJS CONCRETE, DURACRETE, KK MANHOLE & COVERS, TERRA FIRMA, PAVER INDIA, DALAL, UNISTONE, CECO, S&S, MOON LIGHT, SWASTIK, ECOCRETE
23.	GRASS PAVER	UNISTONE, ULTRA, HINDUSTAN, KK, KJS
24.	SFRC/PRECAST C.C. COVERS	KK MANHOLE & COVERS, JAIN, PRAGATI, HINDUSTAN
25.	FLYASH BRICKS	POWER BRICK, YBW PROJECT, ASHTECH INDUSTRIES PVT. LTD.
26.	GLASS MOSAIC TILES	PALLADIO, CORAL, MRIDUL, BISAZZA, MMG TILES
27.	INSULATION FOR PIPE, RUBBER INSULATION	KAIFLEX, ARMAFLEX, CAREFLEX, VIDEOFLEX AFLEX
28.	COPPER TUBES/ PIPES	RAJCO, MEXFLOW, DELHI METAL, ABC
29.	READY MIX PLASTER	BIRLA AEROCON, ULTRATECH, RAMCO, WEBER, LATICRETE
30.	RAISED / CAVITY FLOORING	UNI FLOOR, UNITILE INDIA, TATE, ZTFLOOR, ACCESS FLOOR SYSTEMS
31.	DECK SHEET	JSW, TATA BLUESCOPE, INTERARCH, JSPL, ROOFCLAD
32.	SELF-DRILLING SCREWS	TW BUILDDEX & BOUSTED, CORROSHIELD, ATUL FATERNERS LTD.
	PAINTS	
1.	WATER-PROOFING CEMENT PAINT	ASIAN, BERGER, DULUX
2.	ACRYLIC EXTERIOR PAINT	ASIAN (APEX ULTIMA), BERGER (WEATHER COAT LONGLIFE), DULUX (WEATHER SHIELD POWER FLEX)
3.	SYNTHETIC ENAMEL PAINT	ASIAN (APCOLITE), BERGER (LUXOL GLOSS), DULUX (DULUX GLOSS)
4.	PLASTIC/ACRYLIC EMULSION PAINT	ASIAN (ROYAL SHYAN), BERGER (SILK GALMOUR), DULUX (VELVET TOUCH DIAMOND)
5.	ACRYLIC DISTEMPER	ASIAN (AQUA LOCK ACRYLIC), BERGER (Bison SUPER), DULUX (MAGIC ACRYLIC)
6.	CEMENT PRIMER	ASIAN (DECOPRIME), BERGER (SOLVENT BASE), DULUX (SOLVENT BASE)
7.	WALL PUTTY	BIRLA, J.K., JSW

The Agency is required to get prior approval of Engineer-in-charge for the make of the material to be used in the work. In case of non-availability of material from these manufacturers, the Hon'ble Vice Chancellor, DTU may allow use of alternative BIS approved manufacturer makes.

AS
AS/4

[Signature]
Chief Project Officer
Delhi Technological University